



Republic of the Philippines  
**Department of Education**  
 REGION XII  
**City Schools Division of Kidapawan City**  
 J.P. Laurel St. corner Quirino Drive, Kidapawan City

PROJECT : REPAIR OF CLASSROOM SCHOOL BUILDINGS  
 SCHOOL :  
 OWNER : DEPARTMENT OF EDUCATION  
 SUBJECT : BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
A	<b>GENERAL REQUIREMENTS</b>				
<b>Datu Saliman ES</b>					
<i>Construction of Genderized CR</i>					
	5mm thk x 1.20m x 2.40m Marine plywood	sheets	10.00		-
	0.40mm thk x 10' Corrugated GI Sheets	pcs	10.00		-
	2" x 3" x 8' G-Melina	pieces	10.00		-
	2" x 2" x 10' G-Melina	pieces	10.00		-
	2" x 5" x 10' G-Melina	pieces	5.00		-
	#4 Common Wire Nails	kls	1.00		-
	#3 Common Wire Nails	kls	1.00		-
	#1 Common Wire Nails	kl	1.00		-
	Coarse sand (6-8 cu.m.)	load	1.00		-
	Toilet bowl w/o cover	pieces	2.00		-
	Ga. #16 GI. Tie Wire	kls	1.00		-
	Latex Paint	galloon	10.00		-
	assorted tinting colors	cans	20.00		-
	paint brush #2	pieces	5.00		-
	paint brush #3	pieces	5.00		-
	paint brush #4	pieces	5.00		-
	paint thinner	bottles	10.00		-
	Faucet (plastic)	pieces	3.00		-
	4" x 8" 16" CHB	pieces	250.00		-
	flush door with door knob	pieces	2.00		-
	Type-1P Portland Cement	bags	13.00		-
	¾"Ø PVC Pipe S-1000	length	3.00		-
	¾"Ø x 45° PVC elbow with thread	pieces	3.00		-
	¾"Ø PVC Plastic Tee Connector	pieces	5.00		-
	¾"Ø PVC Elbow without thread	pieces	6.00		-
	Solvent Cement	can	1.00		-
	10mmØ x 6.0m DRB	pieces	20.00		-
	LED bulb 10watts	pieces	3.00		-
	Single switch	pieces	3.00		-
	½" Electrical Tape	rolls	2.00		-
	Tapelon Tape	pieces	2.00		-
	PDX wire #12	meters	10.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<i>Electrical for TLS</i>					

LED bulb 10watts	pcs	16	-
PDX #14	meter	50	-
staple wire 1"	boxes	7	-
2-gang switch	pcs	8	-
junction box with cover	pcs	10	-
4 x 4 Receptacle	pcs	16	-
3-gang convenient outlet (surface type)	pcs	8	-
Electrical Tape	rolls	4	-
<b>Material Cost</b>			-
<b>Labor Cost</b>			-
<b>Total Cost</b>			-
<i>Handwashing Facility</i>			
Faucet plastic	pcs	10	-
¾"Ø PE Pipe SDR 11	meters	100	-
¾"Ø x 90° Elbow coupling	pieces	10	-
Straight connector with thread	pieces	10	-
¾"Ø x 90° PVC Elbow	pieces	1	-
PE Tee connector w/o thread	pieces	10	-
¾"Ø PVC pipe S-1000	length	3	-
Solvent Cement	can	2	-
Tapelon Tape	pieces	5	-
¾"Ø PE Tee Coupling	pieces	1	-
4" x 8" 16" CHB	pieces	204	-
Type-1P Portland Cement	bags	20	-
Fined sand	cubics	2	-
Coarsed sand	loads	2	-
10mmØ x 6.0m DRB	pieces	20	-
0.60m x 0.60m Granite Tiles	pieces	40	-
Tile Grout (2kgs)	bag	1	-
Ga. #16 Gl. Tie Wire	kls	1	-
Cutting disc	pieces	3	-
2" x 2" x 10' Coco Lumber	pieces	10	-
5mm thk x 1.20m x 2.40m Marine plywood	pieces	2	-
<b>Material Cost</b>			-
<b>Labor Cost</b>			-
<b>Total Cost</b>			-
<b>RBA Sabulao ES</b>			
<i>Handwashing Facility</i>			
Type 1 P-Cement	bags	8.00	-
10 mm Ø x 6.0m Deformed Bars	length	8.00	-
2"Ø x 3m PVC Pipe S-1000	length	5.00	-
2"Ø PVC Coupling	pcs	8.00	-
2" x 2" Ø PVC Tee	pcs	3.00	-
1/2 Teflon tape	rolls	5.00	-
2"Ø PE Connector	pcs	6.00	-
Fined Sand	cu.m	1.00	-
Faucet Plastic	pcs	4.00	-
Folding Bed with Foam	set	1.00	-
<b>Material Cost</b>			-
<b>Labor Cost</b>			-
<b>Total Cost</b>			-
<b>F.Suerte ES</b>			
<i>Improvement of School Building</i>			
Type 1 P-Cement	bags	20.00	-
Fined Sand	cu.m	6.00	-
PDX wire #14	box	1.00	-
Electric Staple Wire	boxes	6.00	-

2-Gang Switch	sets	2.00	-
1-Gang Switch	sets	2.00	-
Switch Box	pcs	8.00	-
Electrical Tape	rolls	2.00	-
Junction Box	pc	1.00	-
Cable Clamp (PDX14-2)	pcs	45.00	-
Receptacle ( 2 x 2 )	pcs	6.00	-
2-Gang Convenience Outlet	sets	4.00	-
Star Screw with Bolt (black pntd)	pcs	30.00	-
2"Ø PVC Orange Pipe	length	30.00	-
Flat Latex	gals	20.00	-
Latex (Gloss)	gals	21.00	-
Tinting Color	cans	16.00	-
Enamel Paint	gals	5.00	-
Paint Roller with Tray	pcs	6.00	-
Paint Brush # 4	pcs	8.00	-
Guntacker Staple Wire (21-6mm)	boxes	3.00	-
Caution Tape	rolls	10.00	-
Tarpaulin	pcs	100.00	-
Toilet bowl (Water Closed)	pcs	1.00	-
<b>Material Cost</b>			-
<b>Labor Cost</b>			-
<b>Total Cost</b>			-
<b>Kidapawan City Pilot ES</b>			
<i>Improvement of School Building</i>			
Type 1 P-Cement	bags	20.00	-
Fined Sand	cu.m	4.00	-
#3 CWN	kgs	6.00	-
#2 CWN	kgs	6.00	-
9mm Ø DRB	length	60.00	-
5mm x 1.20m x 2.40m Plywood	sheet	20.00	-
LED Bulb 26 watts	pcs	100.00	-
Plastic Faucet	pcs	120.00	-
1/2" Ø SPR Hose	mtrs	300.00	-
1/2"Ø Gate Valve	pcs	10.00	-
Tefflon Tape	roll	5.00	-
2'x 3' Sink	pcs	100.00	-
2"Ø PVC Elbow	pcs	100.00	-
1/2"Ø x 3.0m PVC Pipe S. 1000	length	70.00	-
1/2"Ø Plastic Tee Connector	pcs	50.00	-
1/2"Ø G.I. Tee Connector	pcs	50.00	-
1/2"Ø G.I. Coupling Connector	pcs	120.00	-
4' x 5' Tarpaulin	pcs	10.00	-
1' x 3' Tarpaulins	pcs	20.00	-
Nylon Rope 37/m	roll	200.00	-
<b>Material Cost</b>			-
<b>Labor Cost</b>			-
<b>Total Cost</b>			-
<b>Nuangan IS</b>			
<i>Improvement of School Building and putting up of Handwashing Facility</i>			
THHN # 14 wire	meter	50.00	-
15 watts LED Bulb	pcs	16.00	-
Switch	set	8.00	-
4-Gang Convenience Outlet (Surface)	set	4.00	-
Electric Staple Wire	box	4.00	-
Electrical Tape	roll	3.00	-
10 mm Ø x 6.0m Deformed Bars	length	10.00	-

	Type 1 P-Cement	bags	12.00		-
	Fine Sand	cu.m	1.00		-
	4" x 8" x 16" CHB	pcs	120.00		-
	0.40m x 0.40m Glazed Tiles	pcs	50.00		-
	Tile Grout	bag	1.00		-
	Faucet Plastic	pcs	6.00		-
	2"Ø x 3m PVC Pipe S-1000	length	5.00		-
	2"Ø PVC Coupling	pcs	12.00		-
	1/2 Teflon tape	rolls	6.00		-
	2"Ø PE Connector	pcs	6.00		-
	2" x 2" Ø PVC Tee	pcs	3.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Malinan ES</b>					
	<i>Improvement of School Building</i>				
	Bulb 10 watts	pcs	10.00		-
	0.40mm THK Corrugated GI Sheet	sheet	11.00		-
	2" X 2" X 8' lumber gemelina	length	40.00		-
	2" X 2" X 8' lumber gemelina	length	2.00		-
	Umbrella Nail	kg	1.00		-
	Common Wire Nail #2	kg	1.00		-
	Common Wire Nail #3	kg	1.00		-
	Concrete Nail #3	kg	1.00		-
	5 mm thk Ordinary Plywood 4' x 8'	pcs	6.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Amas CES</b>					
	<i>Handwashing Facility</i>				
	4" x 8" 16" CHB	pcs	120.00		-
	10mmØ x 6.0m DRB	pcs	10.00		-
	9mmØ x 6.0m DRB	pcs.	10.00		-
	Type-1 Portland Cement	bags	12.00		-
	5mm thk. x 1.20m x 2.40m Ordinary Plywood	pcs	4.00		-
	2 1/2" Common Wire Nail	kgs.	2.00		-
	2"Ø PVC Pipe S-1000	pcs	4.00		-
	2"Ø x PVC Elbow 45 degrees	pcs	20.00		-
	Fined Sand	cu.m	1.50		-
	Faucets Plastic	pcs	10.00		-
	SPR Hose 1/2"	mtrs	150.00		-
	Coupling 2"	pcs	10.00		-
	2"Ø x 2"Ø PVC Tee	pcs	10.00		-
	½" Tapelon Tape	roll	2.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Onica ES</b>					
	<i>Construction of Community Help Desk</i>				
	0.40mm thk. Corrugated GI Sheet	sheet	10		-
	2" x 2" x 8" Gemelina Lumber	pc	42		-
	2" x 3" x 8" Gemelina Lumber	pc	4		-
	Umbrella Nails	kg	1		-
	#2 Common Wire Nail	kg	1		-
	#3 Common Wire Nail	kg	1		-
	#3 Concrete Nail	kg	1		-

	4mm x 1.20m x 2.40m Marine Plywood	sheet	10		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Patadon ES</b>					
<i>Handwashing Facility</i>					
	4" x 8" x 16" CHB	Pcs	75.00		-
	10mmØ x6.0m DRB	Lenth	8.00		-
	9mmØ x 6.0m DRB	Lenth	12.00		-
	Type-1P Portland Cement	Sack	15.00		-
	5mm thk x 1.20m x 2.40m Ordinary Plywood	Pcs	3.00		-
	Faucet Steel	Pcs	10.00		-
	0.40mx 0.40m Ceramic Tile	Pcs	20.00		-
	Tile Grout (2kgs)	Kl	1.00		-
	½"Ø Gate Valve	Pcs	1.00		-
	1"Ø x 90° Elbow	Pcs	3.00		-
	1"Ø x ½"Ø Tee Coupling	Pcs	10.00		-
	4x4 Strainer	Pcs	1.00		-
	½"Ø x 12" G.I Nipple	Pcs	10.00		-
	White Gloss latex	Gal	2.00		-
	#4 Paint Brush	Pcs	3.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>San Roque ES</b>					
<i>Construction of Help Desk Cubicleand Drop Off Point</i>					
	Type 1 P-Cement	bags	32.00		-
	0.40mm thk. Corrugated GI Sheet	sheet	10.00		-
	2" x 2" x8' Gemina Lumber	pc	40.00		-
	Umbrella Nails	kl	1.00		-
	#2 Common Wire Nail	kl	1.00		-
	#3 Common Wire Nail	kl	1.00		-
	#3 Concrete Nail	kl	1.00		-
	4mm thk. x 1.20m x 2.40m Marine Plywood	pc	10.00		-
	bulb 10 watts	pcs	10.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Katipunan ES</b>					
<i>Repair of Classrooms</i>					
	Type 1 P-Cement	bags	32.00		-
	0.40mm thk. Corrugated GI Sheet	sheet	10.00		-
	2" x 2" x8' Gemina Lumber	pc	40.00		-
	Umbrella Nails	kl	1.00		-
	#2 Common Wire Nail	kl	1.00		-
	#3 Common Wire Nail	kl	1.00		-
	#3 Concrete Nail	kl	1.00		-
	4mm thk. x 1.20m x 2.40m Marine Plywood	pc	10.00		-
	bulb 10 watts	pcs	10.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Amazion ES</b>					
<i>Construction of Handwashing Facility</i>					
	Faucet Plastic	pcs	10.00		-

	1/2"Ø x 90deg uPVC Elbow	pcs	12.00		-
	1/2" Ø uPVC Tee	pcs	9.00		-
	1/2" Ø uPVC Coupling	pcs	13.00		-
	1/2"Ø Gate Valve	pcs	2.00		-
	1/2"Ø uPVC Pipe	length	3.00		-
	1/2 Teflon tape	roll	2.00		-
	Solvent Cement	can	1.00		-
	9 mm Ø x 6.0m DRB	length	15.00		-
	Type 1 P-Cement	bags	9.00		-
	Ga. #16 GI Tie Wire	kg	1.00		-
	#4 CW Nails	kg	2.00		-
	#2 1/2 CW Nails	kg	1.00		-
	SPR Hose 1/2	m	10.00		-
	1/2" Ø uPVC Tee Connector	pcs	2.00		-
	0.60m x 0.60m Glazed Tiles	pcs	13.00		-
	1/2" Ø uPVC Red	pc	3.00		-
	Water Resistant	bags	1.00		-
	Fined Sand	cu.m	1.00		-
	2" X 2" X 8' Coco Lumber	length	10.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Mateo ES</b>					
<i>Improvement of School Building</i>					
I. Carpentry Works					
	5mm x 1.20m x 2.40m Plywood	pcs	2.00		-
	2" x 2" x 10' Coco Lumber	length	24.00		-
	2" x 2" x 12' mahogany Lumber	length	12.00		-
	Nail #1 1/2 CWN	kgs	1.00		-
	Nail #2 CWN	kgs	1.00		-
	Nail #2 1/2 CWN	kgs	2.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Sub-total</b>				-
II. Concrete Works					
	Fine sand	cu.m.	2.00		-
	4"x 8" x 16" CHB	pcs	100.00		-
	Type 1- P Cement	bags	60.00		-
	9mm Ø DRB	length	10.00		-
	10mm Ø DRB	length	10.00		-
	floor tiles (0.60 x 0.60)	pcs	25.00		-
	Tile Grout	packs	1.00		-
	Tile Trim	length	6.00		-
	Tile Adhesive	bags	1.00		-
	Coarse Sand	cu.m.	8.00		-
	Fine Screen	mtrs	2.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Sub-total</b>				-
III. Plumbing Works					
	G.I. Pipe 1/2	length	2.00		-
	Faucet	pcs	10.00		-
	Tefflon Tape big	roll	4.00		-
	2"Ø PVC Pipe S 1000	length	4.00		-
	2"Ø PVC T Connector	pcs	2.00		-
	2"Ø PVC L connector	pcs	2.00		-
	1/2"Ø Gate Valve PLASTIC	pcs	1.00		-
	2"Ø SPR Hose	mtrs	30.00		-

	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Sub-total</b>				-
<i>IV. Doors</i>					
	Door w/ Door Knob	set	9.00		-
	Door Jamb	set	9.00		-
	Door Knob	set	9.00		-
	Hinges 3x4	pcs.	27.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Sub-total</b>				-
<i>V. Painting Works</i>					
	QDE Enamel Paint (Mahogany)	gal.	2.00		-
	Paint Brush #3	pcs	2.00		-
	Paint Brush #2	pcs	2.00		-
	Laquer thinner	gal.	2.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Sub-total</b>				-
	<b>Total Cost</b>				-
<b>Kalasuyan ES</b>					
<i>Construction of Waiting Shed</i>					
	Fine Sand	cubic	3.00		-
	Hollow blocks( standard size ) 4"	pcs	70.00		-
	cement	bags	12.00		-
	GI Tube # 2" x 20 sch 40 Economy	L	4.00		-
	defbar / roundbar 10mm	L	12.00		-
	square bar #12	L	12.00		-
	angle bar 18 x 1	L	12.00		-
	GI sheet #12 G26	L	6.00		-
	umbrella nails with wire	kl	4.00		-
	vulcaseal 1/2 liter	pack	1.00		-
	paralux white	gal	1.00		-
	tie wire #16	kl	1.00		-
	welding rod	kl	2.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Lanao CES</b>					
<i>Installation of Portable Handwashing Facility</i>					
	Complete set stainless portable lavatory	unit	8.00		-
	½"Ø PE pipe SDR 11	m.	55.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Singao IS</b>					
<i>Completion of TLS, Ramp and Stage</i>					
	plywood marine 5mm	pcs	36.00		-
	nails no. 4	kls	4.00		-
	nails number 2	kls	4.00		-
	lumber 2x3x8	pcs	70.00		-
	lumber 2x2x10	PCS	8.00		-
	nails number1	kls	2.00		-
	hinges number 3x4	pcs	2.00		-
	electrical tape	pcs	1.00		-
	gate valve 1/2	pcs	1.00		-
	slating paint	quart	1.00		-

	switch	pcs	2.00		-
	steel matting	pcs	2.00		-
	CONVENIENCE OUTLET 4 GANG	pcs	2.00		-
	led bulb ( 15 watts)	pcs	4.00		-
	pdx number 14	m	9.00		-
	cement	bags	58.00		-
	course sand	cu.m	6.00		-
	fine sand	cu.m	10.00		-
	WELDING ROD	kl	1.00		-
	G I PIPE NO. 2	Pc	1.00		-
	Padlock	pcs	2.00		-
	Extension Wire	set	1.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Amas NHS</b>					
<i>Improvement of Classrooms</i>					
	Boysen Latex( White)	gals	20.00		-
	Tinting Colors ( Latex) yellow, blue, green, black , red	cans	25.00		-
	#2 Paint Brush	pcs	2.00		-
	#3 Paint Brush	pcs	2.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Juan Gantuangco SAT</b>					
<i>Construction of Handwashing Facility</i>					
	4" x 8" x 16" CHB	pcs	200.00		-
	10 mm $\varnothing$ x 6.0m DRB	length	15.00		-
	9 mm $\varnothing$ x 6.0m DRB	length	12.00		-
	Type 1 P-Cement	bags	18.00		-
	5mm thk x 1.20m x 2.40m Ordinary Plywood	pcs	2.00		-
	#2½ CW Nails	kg	1.00		-
	2" $\varnothing$ x 3m PVC Pipe S-1000	length	7.00		-
	2" $\varnothing$ x 90deg PVC Elbow	pcs	5.00		-
	2" x 2" $\varnothing$ PVC Tee	pcs	5.00		-
	Vulcaseal	packs	2.00		-
	0.40m x 0.40m Glazed Tiles	pcs	75.00		-
	Tile Grout (2 kg)	bag	1.00		-
	Fined Sand	cu.m	3.50		-
	1/2" $\varnothing$ x 3m PVC Pipe S-1000	length	1.00		-
	Faucet Plastic	pcs	10.00		-
	1" $\varnothing$ PE Tee Plain	pcs	10.00		-
	1" $\varnothing$ PE Coupling	pcs	12.00		-
	½" $\varnothing$ Gate Valve	pc	1.00		-
	1" x 1/2" $\varnothing$ PE Tee	pc	1.00		-
	1/2 Teflon tape	roll	1.00		-
	Solvent Cement	can	1.00		-
	PVC Clamp	pcs	50.00		-
	1" $\varnothing$ x 90deg PE Elbow	pcs	6.00		-
	1" $\varnothing$ Gate Valve	pc	1.00		-
	SPR Hose 1/2	m	2.00		-
	3/4" x 1/2" $\varnothing$ PE Red.Tee	pc	1.00		-
	Strainer	pcs	10.00		-
	<b>Material Cost</b>				-
	<b>Labor Cost</b>				-
	<b>Total Cost</b>				-
<b>Kalaisan NHS</b>					



<i>Installation of Classroom Partition</i>				
	4mm thk x 1.20m x 2.40m Marine Plywood	pcs	56.00	-
	2" x 2" x 8" Lumber	pcs	120.00	-
	#4 Concrete nail	kg	4.00	-
	#1 Finishing Nail	kg	1.00	-
	#2½ Common Wire Nail	kg	6.00	-
	Paint (White Enamel)	gals	16.00	-
	4" Paint Brush	pcs	16.00	-
	Tinting Color Red	cans	3.00	-
	Tinting Color Blue	cans	3.00	-
	Tinting Color Green	cans	3.00	-
	Tinting Color Yellow	cans	3.00	-
	<b>Material Cost</b>			-
	<b>Labor Cost</b>			-
	<b>Total Cost</b>			-
<b>Saniel Cruz NHS</b>				
<i>Construction of Handwashing Facility</i>				
	4" x 8" x 16" CHB	pcs	200.00	-
	Type-1 Portland Cement	bags	20.00	-
	10mmØ x 6.0m DRB	pcs	15.00	-
	9mmØ x 6.0m DRB	pcs	15.00	-
	Plastic Faucets	pcs	10.00	-
	Fined sand	load	1.00	-
	0.40m x 0.40m Ceramic Tiles	pcs	30.00	-
	#1½ Common Wire Nails	kg	1.00	-
	2"Ø PVC Pipe S-1000	Length	3.00	-
	PVC 1/2 (steel)	Length	2.00	-
	Steel Elbow	pcs	20.00	-
	3/4 x 1/2 PE Red. Tee	pcs	10.00	-
	<b>Material Cost</b>			-
	<b>Labor Cost</b>			-
	<b>Total Cost</b>			-
<i>Construction of School Concrete Pathway</i>				
	Type-1 Portland Cement	bags	40.00	-
	Sand and Gravel	load	1.00	-
	Sieve Passing ½"	meters	2.00	-
	# 2 ½ Common Wire Nails	kl	1.00	-
	<b>Material Cost</b>			-
	<b>Labor Cost</b>			-
	<b>Total Cost</b>			-
<b>Mt. Apo NHS</b>				
<i>Construction of Temporary Learning Shelter(TLS)</i>				
	Lumber 4x4x10	pcs	8	-
	Lumber 2x6x12	pcs	16	-
	Lumber 2x4x12	pcs	24	-
	Lumber 2x2x12	pcs	40	-
	G.I. Sheet #12 Gauge 26	pcs	35	-
	Plain Sheet Gauge 24	pc	1	-
	Common Nail #4	kg	4	-
	Common Nail #3	kg	4	-
	Common Nail #2 1/2	kg	3	-
	Hardinail #1	kg	3	-
	Umbrella Nails #2	kg	3	-
	Plywood 5mm	pcs	20	-
	Hinges #3	pcs	6	-
	Hinges #2	pcs	8	-
	Door Handle	pcs	2	-

Safety Hasp	pcs	2		-
Padlock	pcs	2		-
Barrel Bolt	pcs	4		-
Enamel Paint	gallon	4		-
Paint Thinner	gallon	1		-
Paint Brush #4	pcs	4		-
Paint Roller with tray #10	pcs	4		-
<b>Material Cost</b>				-
<b>Labor Cost</b>				-
<b>Total Cost</b>				-

**Mt. Apo NHS-Balabag Ext NHS**

*Improvement of School Building*

<b>I. Concrete Works</b>				
Type 1 P-Cement	bags	40.00		-
4"x 8" x 16" CHB	pcs	500.00		-
10mm Ø DRB	length	25.00		-
9mm Ø DRB	length	25.00		-
Fine Sand	cu.m	8.00		-
Sieve Screen	mtrs	2.00		-
G.a. 16 G.I. Tie Wire	kgs	5.00		-
<b>Material Cost</b>				-
<b>Labor Cost</b>				-
<b>Sub-total</b>				-

<b>II. Carpentry Works</b>				
5mm x 1.20m x 2.40m Plywood	pcs	4.00		-
2" x 2" x 12' G- Melina	length	26.00		-
2" x 2" x 10' G- Melina	length	25.00		-
#3 CWN	kgs	4.00		-
#2 1/2 CWN	kgs	3.00		-
#3 Umbrella Nails	kgs	2.00		-
0.40mm thk Corrugated G.I. Roofing 8ft	pcs	10.00		-
<b>Material Cost</b>				-
<b>Labor Cost</b>				-
<b>Sub-total</b>				-

<b>III. Plumbing Works</b>				
4"Ø PVC Pipe S 1000	length	2		-
1" Tefflon Tape	roll	1		-
4" Ø PVC Elbow	pcs	4		-
Plastic Faucet	pcs	4		-
Toilet Bowl white	pcs	2		-
1/2"Ø PE Pipe	roll	2		-
PVC Compression Equal Tee	pcs	4		-
48MMX20M WaterproofUtility Pro Strength Duct Tape	roll	2		-
<b>Material Cost</b>				-
<b>Labor Cost</b>				-
<b>Sub-total</b>				-
<b>Total Cost</b>				-

**UPPER SINGAO ELEMENTARY SCHOOL**

*Improvement of School Building*

Type-1 Portland Cement	bag	40		-
Sand and Gravel	cu. M.	13		-
1/2"Ø PE Pipe SDR 11	m	41		-
Sink (3x4)	pcs	5		-
Faucet	pcs	5		-
1/2"Ø x 90" PVC Elbow	pcs	5		-
1" x 2" GI square tube	pcs	5		-
Special Welding Rod	kg	1		-

Cutting Disc	pcs	2		-
TTHN #14 wires	m	60		-
Bulb led light 19w	pcs	11		-
Outlet 4-gang surface	pcs	4		-
Switch (double set)	pcs	4		-
<b>Material Cost</b>				-
<b>Labor Cost</b>				-
<b>Total Cost</b>				-

<b>I. MATERIAL COST</b>	-
<b>II. LABOR COST</b>	-
<b>III. TOTAL CONSTRUCTION COST( I + II + III)</b>	-

Prepared:

Recommending Approval:

**ENGR. YOUSOPH T. LINTONGAN**

**REMEGIO H. ORIAS**

Division Engineer

Chief, SGOD

Approved:

**DR. NATIVIDAD G. OCON, CESO VI**

Head of Procuring Entity (HOPE)